

Request for Proposal Number: 23-24

Addendum 4

Date: March 16, 2023

Acknowledgment of Addenda

The undersigned acknowledges receipt of the following addenda to the bidding document:

**THE COMPLETED ACKNOWLEDGEMENT OF ADDENDA FORM
SHOULD BE RETURNED WITH BID RESPONSE PACKAGE: NOT
SENT TO RIPTA SEPARATELY**

NOTE: Failure to acknowledge receipt of all addenda may cause the bid to be considered non-responsive to the solicitation. Acknowledged receipt of each addendum must be clearly established and included with the bid.

Name of Bidder

Street Address

City, State, Zip

Signature of Authorized Official

Date

Request for Proposal Number: 23-24

Addendum 4

Date: March 16, 2023

Notice to Contractor – Contractor Field Quality-Control Testing and Testing Agency:

This notice to contractors is to provide clarification on contractor responsibilities in regard to Specification Division 01 Section 01 40 00 – “Quality Requirements” and Section 01 45 29 – “Testing Laboratory Services”.

The contractor shall be responsible to engage an independent materials testing agent/agency and bear all associated costs for the performance of the following required field inspection, testing and reporting:

1. Subgrade (Pavement, Sidewalk, Structures) – Compact to 95% of maximum density; 1 compaction test per 1000 SF (requires field sampling in-situ soil and laboratory proctor test)
2. Gravel Borrow Subbase
 - a. Pavement – Compact to 95% of maximum density; 1 compaction test per 1000 SF
 - b. Sidewalk, Curbing – Compact to 95% of maximum density; 1 compaction test per 500 SF
3. Concrete (Pavement, Sidewalk, Structures) – Concrete temperature, ambient air temperature, % air content, slump, compressive strength (1 set of standard 4” x 8” cylinders per 150 CY, but not less than one (1) set per day)
4. Bituminous Asphalt Pavement – Compact to 92% of the theoretical maximum density obtained at the plant and will be determined using a nuclear density gauge or in-place cores; 1 compaction test per 1000 SF per lift

All testing procedures shall comply with the project specifications and RIDOT Standard Specifications for Road and Bridge Construction as referenced.

Contractor shall be responsible to furnish inspection and testing reports to Owner within 7 calendar days of the Work. Refer to Section 01 40 00, Part 3.2 – “Test and Inspection Log” for additional information.